

**BID SPECIFICATIONS
TOWN OF ASHFORD HIGHWAY BARN
SIDING AND WINDOW REPLACEMENT**

OPTION 1

- Labor and Material to replace seven (7) fixed insulated casement vinyl windows—approximately 44" x 48" (contractor to verify size)
- Trim all exposed wood with 29 GA white steel trim and solar seal caulking
- Remove existing steel windows that cover three (3) windows that have already been changed in Food Pantry.
- Trim all exposed wood with 29 GA white steel trim

OPTION 2

- Labor and material to reside one (1) 50' East end wall, one (1) 50' West end wall and one (1) South sidewall (overhead door side)
- Furring strips installed over existing steel siding .60 CCA Pressure treated 1" x 3" or cucumber tulip approximately 28" O.C.
- New siding to be 29 GA 40 year painted Gavalume-color to be determined
- All new 29 GA painted trim-outside corners-based-J Channel one piece overhead jamb trim
- Frame overhead headers to be covered with new steel siding
- All fasteners to be painted stainless steel
- Replace all overhead door weather seals
- Lengthen service conduit to accommodate new steel siding to go behind riser pipe